



QUANTITY TAKEOFF REPORT

Powered by SSN Corporation · www.ssncorporation.com

Client Name	Bishal Ghimire	Project Name	Cranberry House
Date	24 Jun 2026	SSN Project No	2026-0048
Website	https://qtakeoff.ai	Email	bishal.ghimire09870@gmail.com

DIVISION COST SUMMARY

Div.	Division Name	Mat. O&P (\$)	Labor O&P (\$)	Equip. O&P (\$)	Total O&P (\$)
03	Concrete	7,371.28	5,286.91	898.96	13,557.15
04	Masonry	11,945.34	12,879.45	2,004.51	26,829.30
06	Wood and Plastics	113,101.69	97,101.29	9,783.79	219,986.78
07	Thermal and Moisture Protection	49,545.17	36,991.26	3,494.92	90,031.35
08	Openings	22,250.03	17,489.99	2,075.01	41,815.03
09	Finishes	95,927.48	90,804.36	7,692.87	194,424.71
10	Specialties	2,610.43	2,253.50	236.54	5,100.48
31	Earthwork	2,837.97	3,255.97	1,154.99	7,248.92
33	Utilities	1,650.66	1,540.62	220.09	3,411.36
	GRAND TOTAL	307,240.04	267,603.36	27,561.68	602,405.08

Materials Summary by CSI Division

Spec No.	Specification	Unit	Qty	Qty + Waste	Mat. O&P (\$)	Labor O&P (\$)	Equip. O&P (\$)	Total O&P (\$)	Description
Division 03 — Concrete									
03 15 19	Cast-In Concrete Anchors	EA	83	83	415.00	415.00	60.59	890.59	1/2" dia. Anchor bolts @ 6' o.c.
03 20 00	Concrete Reinforcing	LB	85	85	286.45	268.60	43.35	598.40	#4 reinforcement bottom
03 20 00	Concrete Reinforcing	LB	166	166	1,593.60	1,480.72	227.42	3,301.74	#6 @ 32" o.c. reinforcement
03 22 00	Fabric and Grid Reinforcing	SF	470	517	584.21	398.09	93.06	1,075.36	Welded wire fabric, plain, sheets, 6 x 6 - W1.4 x W1.4 (10 x 10)
03 30 00	Cast-in-place Concrete	CY	49	53.9	4,452.68	2,695.00	468.93	7,616.61	3000 psi in footing
03 30 00	Cast-in-place Concrete	CY	6	6.6	39.34	29.50	5.61	74.45	4" thick concrete
Division 03 Subtotal					7,371.28	5,286.91	898.96	13,557.15	
Division 04 — Masonry									
04 05 16	Masonry Grout	CY	6	6.6	1,320.00	1,225.69	188.56	2,734.25	Grout, concrete masonry unit (CMU) cores, 10" thick, 0.340 C.F./S.F., pumped, excludes blockwork
04 22 00	Concrete Unit Masonry	CY	1080	1,188	5,108.40	6,795.36	1,140.48	13,044.24	8" CMU
04 22 00	Concrete Unit Masonry	SF	415	456.5	2,898.78	2,656.83	438.24	5,993.85	12" CMU
04 42 00	Exterior Stone Cladding	SF	263	289.3	2,618.17	2,201.57	237.23	5,056.96	georgetown run morning aspen fire rated flat stone veneer, model# fr-gr-ma-f or approved equal.
Division 04 Subtotal					11,945.34	12,879.45	2,004.51	26,829.30	
Division 06 — Wood and Plastics									
06 10 00	Rough Carpentry	LF	110	121.0	627.99	514.25	79.86	1,222.10	Ledger Board Continuous 1" X 9 1/4"
06 11 00	Wood Framing	EA	83	83	1,521.39	1,660.00	138.61	3,320.00	2 X 6 @ 16" o.c.
06 11 00	Wood Framing	EA	28	28	118.44	134.40	11.20	264.04	2X10 ceiling joists @ 16" o.c.
06 11 00	Wood Framing	EA	6	6	24.90	28.74	2.88	56.52	2X8 ceiling joists @ 16" o.c.
06 11 00	Wood Framing	LF	330	363.0	1,909.38	1,553.64	239.58	3,702.60	Bottom plate with double top plate 2 X 6
06 11 00	Wood Framing	SF	4560	5,016	33,456.72	28,591.20	2,407.68	64,455.60	2 X 10 joists @ 16" o.c.
06 11 00	Wood Framing	SF	139	152.9	2,802.66	3,058.00	255.34	6,116.00	2 X 6 @ 16" o.c.
06 11 00	Wood Framing	SF	114	125.4	2,298.58	2,508.00	209.42	5,016.00	2 X 6@ 16" o.c.
06 11 00	Wood Framing	SF	1011	1,112.1	11,699.29	9,519.58	1,467.97	22,686.84	Bottom plate with double top plate 2 X 6

Spec No.	Specification	Unit	Qty	Qty + Wastage	Mat. O&P (\$)	Labor O&P (\$)	Equip. O&P (\$)	Total O&P (\$)	Description
06 15 00	Wood Decking	SF	104	114.4	715.00	605.18	88.09	1,408.26	Wood floor decking, cedar planks, 4" thick
06 16 00	Sheathing	SF	570	627	1,504.80	1,272.81	100.32	2,877.93	3/4" OSB Board Sheathing
06 16 00	Sheathing	SF	1836	2,019.6	4,847.04	4,099.79	323.14	9,269.96	7/16" OSB Sheathing
06 16 13	Insulating Sheathing	SF	4560	5,016	6,069.36	4,414.08	351.12	10,834.56	7/16" OSB Sheathing
06 16 23	Subflooring	SF	1460	1,606.0	3,854.40	3,244.12	305.14	7,403.66	Subfloors, plywood, CDX, 3/4" thick
06 16 26	Underlayment	SF	2280	2,508	6,019.20	5,066.16	476.52	11,561.88	Polyglass Polystick 40 mil
06 18 13	Glued-Laminated Beams	LF	54	59.4	3,564.00	2,970.00	445.50	6,979.50	(3)-2X12s SYP #2 Dropped Beam
06 18 13	Glued-Laminated Beams	LF	13	14.3	715.00	605.03	87.95	1,407.98	3-2X12 #SPF Beam
06 22 00	Millwork	LF	462	508.2	18,274.87	15,987.97	1,717.72	35,980.56	Moldings, base, caps, 3/4" x 1-3/4", poplar
06 43 13	Wood Stairs	EA	25	25	7,500.00	6,500.00	500.00	14,500.00	11" tread=25 and 7" riser=26
06 43 16	Wood Railings	LF	93	102.3	3,678.71	3,218.36	345.77	7,242.84	Railings, custom design, architectural grade, hardwood, max
06 44 39	Wood Posts and Columns	EA	4	4	147.36	136.84	16.84	301.04	4 X 4 stair timber post
06 44 39	Wood Posts and Columns	EA	15	15	552.60	513.15	63.15	1,128.90	4 X 4 timber post for railing, 3'6" height
06 44 39	Wood Posts and Columns	EA	10	10	800.00	600.00	100.00	1,500.00	8 X 8 timber post ,9' height
06 44 39	Wood Posts and Columns	EA	5	5	400.00	300.00	50.00	750.00	8 x 8 timber post #2 ground contact pressure-treated southern pine
Division 06 Subtotal					113,101.69	97,101.29	9,783.79	219,986.78	
Division 07 — Thermal and Moisture Protection									
07 21 00	Thermal Insulation	SF	5220	5,742.0	20,613.78	14,182.74	1,205.82	36,002.34	R-19 Fiberglass batt
07 21 00	Thermal Insulation	SF	2280	2,508	3,034.68	2,081.64	175.56	5,291.88	R-30 insulation
07 21 16	Blanket Insulation	SF	570	627	746.13	514.14	43.89	1,304.16	R-10 insulation
07 26 00	Vapor Retarders	SF	840	924.0	877.80	766.92	92.40	1,737.12	4 mil vapor barrier
07 31 13	Asphalt Shingles	SF	2280	2,508	6,044.28	4,940.76	451.44	11,436.48	Asphalt shingles, standard, laminated multi-layered shingles, class 3, 260-300 lb/sq, pneumatic nailed
07 46 46	Fiber-Cement siding	SF	1742	1,916.2	12,608.60	9,983.40	1,053.91	23,645.91	Fiber cement siding, shingle siding, 48" X 15-1/4" panels, 7" exposure
07 46 46	Fiber-Cement siding	SF	570	627	4,106.85	3,304.29	344.85	7,755.99	hardie plank hz5 8.25 in. X 144 in. statement collection timber bark cedarmill fiber cement lap siding

Spec No.	Specification	Unit	Qty	Qty + Waste	Mat. O&P (\$)	Labor O&P (\$)	Equip. O&P (\$)	Total O&P (\$)	Description
07 46 46	Fiber-Cement siding	SF	210	231.0	1,513.05	1,217.37	127.05	2,857.47	hardie trim hz5 1 in. x 9.25 in. x 12 ft. statement collection arctic white roughsawn fiber cement trim board
Division 07 Subtotal					49,545.17	36,991.26	3,494.92	90,031.35	
Division 08 — Openings									
08 10 00	Doors and Frames	EA	1	1	850.00	650.00	90.00	1,590.00	2'6" X 8'5" sliding Door on both panels
08 10 00	Doors and Frames	EA	2	2	1,800.00	1,400.00	150.00	3,350.00	4'3" X 8'5" Sliding Door on both panels
08 11 00	Metal Doors and Frames	EA	3	3	750.00	600.00	60.00	1,410.00	3' X 8'5" Door
08 11 16	Aluminium Doors and Frames	EA	6	6	1,500.00	1,200.00	100.02	2,800.02	2'6" X 8'5" Door
08 11 16	Aluminium Doors and Frames	EA	1	1	350.00	280.00	30.00	660.00	3'6" X 10'6" Door
08 11 16	Aluminium Doors and Frames	EA	3	3	5,100.00	3,900.00	540.00	9,540.00	6' X 10'6" Door
08 11 16	Aluminium Doors and Frames	EA	1	1	400.00	320.00	40.00	760.00	8' X 8'5" Door
08 14 00	Wood Doors	EA	1	1	900.00	700.00	75.00	1,675.00	6'X 8'5" Door
08 14 00	Wood Doors	EA	2	2	800.00	640.00	80.00	1,520.00	8'X 8'5" Door
08 51 13	Aluminium Windows	EA	4	4	1,000.00	800.00	90.00	1,890.00	1'6" X 6' Window
08 51 13	Aluminium Windows	EA	2	2	550.00	450.00	50.00	1,050.00	2' X 6' Window
08 51 13	Aluminium Windows	EA	3	3	800.01	650.01	80.01	1,530.03	3' X 3' Window
08 51 13	Aluminium Windows	EA	6	6	2,200.02	1,699.98	199.98	4,099.98	3'11" X 5' Window
08 51 13	Aluminium Windows	EA	2	2	750.00	600.00	70.00	1,420.00	4' X 6' Window
08 51 13	Aluminium Windows	EA	2	2	1,100.00	900.00	100.00	2,100.00	4'10" X 4'10" X 6'10" Triangular window
08 51 13	Aluminium Windows	EA	1	1	400.00	300.00	40.00	740.00	5' X 5' window
08 51 13	Aluminium Windows	EA	2	2	850.00	700.00	80.00	1,630.00	5'4" x 1' x 5'6" x 1' x 4'11"Left trapezoidal window
08 51 13	Aluminium Windows	EA	2	2	850.00	700.00	80.00	1,630.00	5'4" x 1' x 5'6" x 1' x 4'11"Right trapezoidal window
08 51 13	Aluminium Windows	EA	2	2	1,300.00	1,000.00	120.00	2,420.00	7'10" X 6' Window
Division 08 Subtotal					22,250.03	17,489.99	2,075.01	41,815.03	
Division 09 — Finishes									
09 29 00	Gypsum Board	SF	10814	11,895.4	71,967.17	61,142.36	5,471.88	138,581.41	1/2" gypsum board

Spec No.	Specification	Unit	Qty	Qty + Waste	Mat. O&P (\$)	Labor O&P (\$)	Equip. O&P (\$)	Total O&P (\$)	Description
09 30 00	Tiling	SF	218	239.8	1,436.40	1,196.60	119.90	2,752.90	Ceramic tile, for floors, specialty type, decorator finish, 4-1/4" x 4-1/4"x 1/2"
09 64 29	Wood Strip and Plank Flooring	SF	1432	1,575.2	11,089.41	9,403.94	1,008.13	21,501.48	Wood flooring, parquetry, oak, plain pattern, 5/16" thick, excl. finish
09 70 00	Wall Finishes	SF	540	594	5,375.70	4,520.34	487.08	10,383.12	Ready-mix stucco patch
09 91 00	Painting	SF	5508	6,058.8	6,058.80	14,541.12	605.88	21,205.80	Dry fall painting, ceilings, concrete or textured plaster, two coat, spray
Division 09 Subtotal					95,927.48	90,804.36	7,692.87	194,424.71	
Division 10 — Specialties									
10 26 16.16	Protective Corridor Handrails	LF	96	105.6	2,610.43	2,253.50	236.54	5,100.48	handrails @ 6" o.c.
Division 10 Subtotal					2,610.43	2,253.50	236.54	5,100.48	
Division 31 — Earthwork									
31 23 16	Excavation	CY	76	83.6	2,508.00	2,926.00	1,045.00	6,479.00	Excavation for Foundation
31 23 23	Fill	CY	9	9.9	329.97	329.97	109.99	769.92	Fill of gravel in the foundation
Division 31 Subtotal					2,837.97	3,255.97	1,154.99	7,248.92	
Division 33 — Utilities									
33 41 13.13	Foundation Drainage Piping	LF	164	180.4	1,650.66	1,540.62	220.09	3,411.36	4" perforated pipe
Division 33 Subtotal					1,650.66	1,540.62	220.09	3,411.36	

Materials O&P	\$307,240.04
Labor O&P	\$267,603.36
Equipment O&P	\$27,561.68
GRAND TOTAL — All Divisions	\$602,405.08

STANDARD ABBREVIATIONS

Abbr.	Definition	Abbr.	Definition	Abbr.	Definition
AACE	Association for the Advancement of Cost Engineering	ACT	Acoustical Ceiling Tile	AHU	Air Handling Unit
AL	Aluminum	ALUM	Aluminum	ASI	Architect Supplemental Instruction
ATS	Automatic Transfer Switch	BM	Benchmark	BMP	Best Management Practice
BTU	British Thermal Unit	CF	Cubic Foot	CFM	Cubic Feet per Minute
CIP	Cast-in-Place	CMU	Concrete Masonry Unit	CPT	Carpet
CSI	Construction Specifications Institute	CY	Cubic Yard	EA	Each
EMT	Electrical Metallic Tubing	FCU	Fan Coil Unit	FFE	Furniture Fixtures Equipment
FRP	Fiberglass Reinforced Panel	GA	Gauge	GMP	Guaranteed Maximum Price
GPM	Gallons per Minute	GWB	Gypsum Wall Board	HSS	Hollow Structural Section
HVAC	Heating Ventilation AC	LB	Pound	LF	Linear Foot
LS	Lump Sum	LVT	Luxury Vinyl Tile	M/H	Man-hour
MDF	Medium Density Fiberboard	MEP	Mechanical, Electrical, Plumbing	PCC	Plain Cement Concrete
PEX	Cross-linked Polyethylene	PSI	Pounds per Square Inch	PT	Pressure Treated / Paint
PVC	Polyvinyl Chloride	RCP	Reflected Ceiling Plan	ROW	Right of Way
RR	Rebar	RTU	Roof Top Unit	SF	Square Foot
SOV	Schedule of Values	SS	Stainless Steel	SWPPP	Stormwater Pollution Prevention Plan
SY	Square Yard	T&G	Tongue and Groove	T&M	Time and Material
TBC	Top of Curb	TBD	To Be Determined	TESC	Temporary Erosion and Sediment Control
TON	Short Ton	UPS	Uninterruptible Power Supply	VCT	Vinyl Composition Tile
VFD	Variable Frequency Drive	WD	Wood	WWF	Welded Wire Fabric
O&P	Overhead and Profit	Mat.	Material	Equip.	Equipment

GENERAL NOTES AND ASSUMPTIONS

1. The quantity estimate is based on the plans dated. All estimated quantities are approximate and may vary slightly in the field depending on the Contractor's means, methods, and construction procedure
2. The estimate has been prepared following the standard CSI MasterFormat
3. The takeoff generally excludes items not clearly shown on the plans unless specifically noted. Waste factors have been included where applicable
4. The quantity takeoff includes all demolition quantities, including haul-off and disposal, unless noted otherwise
5. This quantity document serves as an estimate for the Contractor or Owner and does not constitute a bid set. The Engineer of Record must review and sign these estimates for them to be used as part of the bid documents

DISCLAIMER

DISCLAIMER: This quantity takeoff report has been prepared using AI-assisted technology and blueprint analysis. While every effort has been made to ensure accuracy, SSN Corporation makes no warranties, expressed or implied, regarding the completeness or accuracy of the quantities provided herein. This report is intended for estimating purposes only and should be verified by qualified professionals before use in final bidding or construction. Users assume all responsibility for verification of quantities and dimensions. SSN Corporation shall not be liable for any errors, omissions, or discrepancies in the quantities presented in this report